



WIDTH	LENGTH	HEIGHT (PERMS)	TOTAL STAGE SQUARE FOOTAGE	FLOOR TYPE	DOOR (WxH)
123'8"	151'10"	24'	16,611	CEMENT	16' X 16'

*Dimensions are for overall stage size and do not take into account stage irregularities. Production company representative should verify dimensions for particular applications.

STAGE SPECIFICATION - STAGE 19

STAGE SPECIFICATIONS

WIDTH - 123'8"

LENGTH - 151'10"

HEIGHT - 24'

FIRE LANE - 4'

TOTAL SQUARE FOOTAGE - 16,611

ELEPHANT DOOR - 16' X 16'

OCCUPANCY LOAD - 460

POWER

POWER/AMPS - 120-208V / 4,800A

DISCONNECTS PER STAGE - 4

HVAC

HVAC - FULLY SELF CONTAINED (75 TON COOLING CAPACITY)

REDLIGHT CONTROL - YES

BELL & LIGHT SYSTEM - YES

FLEX DUCT CONNECTION - YES

EXHAUST FANS - YES

STAGE EXTRAS

RAMP LOADING - YES

MOTORIZED ELEPHANT DOOR - YES

PIPE GRID PSF - 15

WATER AVAILABLE OUTSIDE - YES

OF PARKING SPACES - 44

*Dimensions are for overall stage size and do not take into account stage irregularities. Production company representative should verify dimensions for particular applications.